



Works Notification

October 2016

Gold Coast Light Rail Stage 2

BIGGERA CREEK BRIDGE CONSTRUCTION



Artist's impression

From 27 October 2016, work will commence to construct the Biggera Creek Bridge, weather and construction conditions permitting.

Work will involve:

- Delivery of machinery such as excavators, cranes, concrete trucks and pumps via the Smith Street Motorway
- Piling (bored) activities will commence from 27 October for a period of up to three weeks
- Delivery of bridge beams will occur in early 2017.

Bored piling involves boring a hole into the ground with large machinery, installing steel reinforcement, filling the bore hole with concrete to form a pile and is a common technique used to construct buildings and bridges.

The Biggera Creek Bridge will include six spans for a total length of 120 metres. It will include 14 bored piles and 84 deck units weighing about 25 tonnes each.

What to expect

- Increased levels of noise and vibration from machinery
- Dust associated with construction activities – water trucks will be onsite to minimise dust
- Increased construction vehicle movements in the area
- Construction work will occur between 7:00am and 6:00pm, Monday to Saturday. Workers may arrive onsite by 6.00am to prepare for the day's activities.

Every effort will be made to minimise construction impacts and monitoring will be carried out during piling works. We appreciate your patience during this important work and will continue to update you as work progresses.

Contact the project team



If you have any questions or would like to register for more information, please contact the CPB Contractors Project Team on **1800 425 799*** or email **gclrstage2@cpbcon.com.au**. Visit **www.gclrstage2.com.au** anytime for more information and updates.

** Free call within Australia. Call charges may apply from mobile or pay phones.*

Subscribing to receive project updates is a convenient way to obtain information about the project and work happening in your area. To subscribe, simply visit our website and look for the 'sign up' form on the 'contact' page.

Project information

Gold Coast Light Rail Stage 2 involves the design and construction of a new 7.3km route which runs from Helensvale heavy rail station adjacent to the Gold Coast Line, then adjacent to the Smith Street Motorway to connect with Stage 1 at the Gold Coast University Hospital light rail station.

GoldlinQ's construction contractor CPB Contractors commenced construction in July 2016 and are committed to completing the project in time for the Gold Coast 2018 Commonwealth Games.



Australian Government

BUILDING OUR FUTURE

CITY OF
GOLDCOAST™

GoldlinQ
Gold Coast Light Rail



Queensland Government