



Works Notification

October 2016

Gold Coast Light Rail Stage 2

CONNECTION OF GOLD COAST UNIVERSITY HOSPITAL STATION WITH STAGE 2



Artist's impression Gold Coast University Hospital station

Work to connect the existing station at the Gold Coast University Hospital to Stage 2 of the light rail will commence on Friday 11 November 2016 and continue until March 2017.

Work will involve:

Tunnel work

- Demolition of a section of the existing retaining wall near the traffic signals on the corner of Olsen Avenue and Parklands Drive to allow for installation of the tracks. The northern side of the footpath on Parklands Drive from Olsen Avenue towards Hospital Boulevard will be closed during this work. Pedestrians will be directed to the southern side of Parklands Drive.
- Work on a bored piling* retaining wall will commence from mid-November 2016 for a period of up to six weeks.
- Shotcreting (a sprayed concrete finish) the tunnel face.
- Use of crane and elevated working platform.
- Installation of precast concrete fascia panels inside the tunnel.

*Bored piling involves boring a hole into the ground with large machinery, installing steel reinforcement, filling the bore hole with concrete to form a pile and is a common technique used to construct buildings.

Station work

Part of the existing northern platform in the station will be removed in late January 2017 to expose the second light rail track underneath.

Once the northern platform is removed, passengers will only be able to disembark on the southern platform. Signage will be in place to direct passengers.

Station work from January to March 2017

- Installation of temporary barriers and fencing.
- Removal of the existing temporary platform on the northern side of the station.
- Removal of concrete sections to enable the installation of tactile indicators, line marking, pedestrian crossing signals and handrails.
- Installation of signage.

More information about the station work will be provided closer to the time.

Every effort will be made to keep construction impacts to a minimum. We appreciate your patience during these important works and will continue to update you as work progresses.

Contact the project team



If you have any questions or would like to register for more information, please contact the CPB Contractors Project Team on **1800 425 799*** or email **gclrstage2@cpbcon.com.au**. Visit **www.gclrstage2.com.au** anytime for more information and updates.

** Free call within Australia. Call charges may apply from mobile or pay phones.*

Subscribing to receive project updates is a convenient way to obtain information about the project and work happening in your area. To subscribe, simply visit our website and look for the 'sign up form' on the 'contact' page.

Project information

Gold Coast Light Rail Stage 2 involves the design and construction of a new 7.3km route which runs from Helensvale heavy rail station adjacent to the Gold Coast Line, then adjacent to the Smith Street Motorway to connect with Stage 1 at the Gold Coast University Hospital light rail station.

GoldlinQ's construction contractor CPB Contractors commenced construction in July 2016 and are committed to completing the project in time for the Gold Coast 2018 Commonwealth Games.



Australian Government

BUILDING OUR FUTURE

CITY OF
GOLD COAST™

GoldlinQ
Gold Coast Light Rail



Queensland Government